OpenBuildingControl

Michael Wetter
Philip Haves
Jianjun Hu
Milica Grahovac

November 2, 2017



Lawrence Berkeley National Laboratory


Presentation Contents

- Guideline 36 implementation (Jianjun & Milica)
- Case study:
 See https://github.com/lbl-srg/obc/tree/master/meetings/2017-11-02-team for report
- Updates to CDL (Michael)
- Verification of requirements
- Upcoming deadlines.
 See https://github.com/lbl-srg/obc/wiki/2017-11-02-team-meeting-agenda#agenda
- Next steps
 - See https://github.com/lbl-srg/obc/wiki/2017-11-02-team-meeting-agenda#agenda
- Other feedback/discussions?

Guideline 36 implementation (Jianjun and Milica)

Implement sequences with CDL

ASHRAE Guideline 36




ASHRAE Guideline 36P, High Performance Sequences of Operation for HVAC systems, First Public Review Draft. ASHRAE, June 2016

Implementation using CDL







```
Buildings.Controls.OBC.CDL.Interfaces.RealInput VOut_f
 final unit="m3/s",
 final quantity="VolumeFlowRate")
  "Measured outdoor volumetric airflow rate"
Buildings.Controls.OBC.CDL.Interfaces.RealInput VOutMin
 final unit="m3/s",
  final quantity="VolumeFlowRate")
  "Minimum outdoor volumetric airflow rate setpoint"
Buildings.Controls.OBC.CDL.Interfaces.IntegerInput uOpe
  "AHU operation mode status signal"
Buildings.Controls.OBC.CDL.Interfaces.IntegerInput uFr
  "Freeze protection status signal"
Buildings.Controls.OBC.CDL.Interfaces.BooleanInput uSur
  "Supply fan status signal"
Buildings.Controls.OBC.CDL.Interfaces.RealOutput yOutDate
  final min=outDamPhyPosMin,
 final max=outDamPhyPosMax,
 final unit="1")
  "Minimum outdoor air damper position limit"
  日;
```





Implement sequences with CDL


Organize sequences package according to Guideline 36 structure














Implement sequences with CDL

Documented and validated sequences







Buildings.Controls.OBC.ASHRAE.G36_PR1.TerminalUnits.Reheat.DamperValve

Updates to CDL (Michael)

CDL changes compared to last meeting

CDL language changes

Now allow calculations in parameter assignments: E.g.,

```
parameter Real pRel(unit="Pa") = 50
     "Static pressure difference at damper";
CDL.Logical.Hysteresis hys(
uLow = pRel-25,
uHigh = pRel+25) "Hysteresis for fan control";
```

Now allow conditional removal of blocks and connectors:

```
parameter Boolean use_enthalpy = true
    "Set to true to use outdoor air enthalpy";

CDL.Interfaces.RealInput hOut if use_enthalpy
    "Outdoor air enthalpy";
```


CDL library additions (which were required during the implementation of guideline 36):


- conversion to/from integer
- truncation of signals
- addition of 3 signals (real, integer)
- integer comparison

Requirements verification (Michael)

Goal is to (semi-)automatically test requirements during design and commissioning, and possibly also during continuous operation


- M3.1 By Q5, demonstrate with an emulated control response that the controls verification can signal satisfied, undecided, and violated test results.
- M3.2 By Q6, demonstrate with an actual measured control response that the controls verification can signal satisfied, undecided, and violated test results.






Problem: How do we verify 100s to 1000s of trajectories, and identify which one(s) cause (first) a problem?


Are these room temperatures satisfactory?



Is this damper control signal stable?




Approach: Instrument the control with verification tests




Verification of room air temperature of east zone

Requirement: Room air temperature shall be within (TSet + 0.5 K) for at least 45 min within each 60 min window.



Verification of east zone damper signal

Requirement: Damper signal shall not oscillate more than 4 times per hour between +/- 0.025 (for a 2 minute sample period)



Verification tests

- M3.1 By Q5, demonstrate with an emulated control response that the controls verification can signal satisfied, undecided, and violated test results.
- M3.2 By Q6, demonstrate with an actual measured control response that the controls verification can signal satisfied, undecided, and violated test results.

Need input from team for what requirements shall be verified. For example

- how well shall set points be tracked?
- when shall cycling equipment be flagged?
- when shall control signals be flagged as oscillatory?

•

Then, can build a requirements library for use in projects.

81.2 % of Guideline36 requirements are satisfied at time = 1.8144e+07 s

Requirements violated (3 of 16)

Observation	Requirement	First violation at	Description
VAV terminal box	conVAVEas.reqTRooCoo	1.74868e+07 s	Room air temperature maintains cooling setpoint
VAV terminal box	conVAVSou.reqTRooCoo	1.75913e+07 s	Room air temperature maintains cooling setpoint
VAV terminal box	conVAVWes.reqTRooCoo	1.77736e+07 s	Room air temperature maintains cooling setpoint

Requirements untested (0 of 16)

None

Requirements satisfied (13 of 16)

Observation	Requirement	Description
VAV terminal box	conVAVCor.reqTRooCoo	Room air temperature maintains cooling setpoint
VAV terminal box	conVAVCor.reqTRooHea	Room air temperature maintains heating setpoint
VAV terminal box	conVAVCor.reqYDam	VAV damper signal stable
VAV terminal box	conVAVEas.reqTRooHea	Room air temperature maintains heating setpoint
VAV terminal box	conVAVEas.reqYDam	VAV damper signal stable
VAV terminal box	conVAVNor.reqTRooCoo	Room air temperature maintains cooling setpoint
VAV terminal box	conVAVNor.reqTRooHea	Room air temperature maintains heating setpoint
VAV terminal box	conVAVNor.reqYDam	VAV damper signal stable
VAV terminal box	conVAVSou.reqTRooHea	Room air temperature maintains heating setpoint
VAV terminal box	conVAVSou.reqYDam	VAV damper signal stable
VAV terminal box	conVAVWes.reqTRooHea	Room air temperature maintains heating setpoint
VAV terminal box	conVAVWes.reqYDam	VAV damper signal stable
AHU	reqTFre	Mixed air temperature above freezing